Graystone Flatwork LLC

Driveways · Patios · Sidewalks

7340 Quarry Line Rd
Prairie Bluff, KS 66000
(316) 555-0145 · office@graystone.example

INVOICE

No. **INV-0715**
Date October 30, 2026
Terms Due within 7 days · November 6, 2026

BILL TO

Dwight Lambert
509 Sumac St
Prairie Bluff, KS 66000
(316) 555-0104 · d.lambert@example.com

Permit: ROW-26-0412 (apron in city right-of-way)

Driveway replacement — 24 × 30 ft, 4-inch slab

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Demolish and haul off existing driveway	720	sq ft	$1.75	$1,260.00
Grade and compact base, 4 in. crushed stone	720	sq ft	$1.10	$792.00
Ready-mix concrete, 4,000 psi with fiber 9.5 cu yd delivered (8.9 cu yd calculated plus overage)	9.5	cu yd	$168.00	$1,596.00
#3 rebar at 18 in. on center, on chairs	720	sq ft	$0.85	$612.00
Place, finish and broom texture	720	sq ft	$3.25	$2,340.00
Saw-cut control joints	1	job	$180.00	$180.00
Expansion joint at garage and sidewalk	54	lin ft	$2.50	$135.00
City right-of-way permit (passed through at cost)	1	ea	$75.00	$75.00

Subtotal	$6,990.00
Sales tax (example rate 7.5%)	$119.70
Total	**$7,109.70**
Deposit received Oct 16 (bank transfer)	−$2,500.00
Balance due	**$4,609.70**

NOTES AND TERMS

- Keep vehicles off the new slab until the date written on your door tag; foot traffic is fine sooner.
- Control joints are placed so shrinkage cracks happen at the joints. Hairline cracks inside a panel aren't a structural defect.
- A penetrating sealer is recommended once the slab has cured; we can quote it separately.

How to pay: Bank transfer (ACH) or card through the pay link, or check.

Customer signature — work completed

Date

Sample invoice — every name, address and price on it is fictional, and the tax is an example: which lines are taxable depends on your state.