Wattleby Electric LLC

Licensed electrical contractor · Lic. #EC-00000

48 Commerce Loop
Oak Haven, GA 30500
(706) 555-0128 · office@wattleby.example

ESTIMATE

No. **EST-0774**
Date November 9, 2026
Valid until December 9, 2026

PREPARED FOR

Greta and Sam Novak
2207 Old Ferry Rd
Oak Haven, GA 30500
(706) 555-0184 · novak.house@example.com

Service upgrade — 100 A to 200 A panel and meter base

Replace the existing 100 A panel and meter base with a 200 A service; transfer and label all existing circuits; update grounding and bonding; add whole-home surge protection. We coordinate the utility disconnect and reconnect.

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
200 A main breaker panel, 40 spaces	1	ea	$640.00	$640.00
200 A meter base and service entrance conductors	1	set	$780.00	$780.00
Grounding electrode system update Ground rods and bonding as required	1	job	$340.00	$340.00
Whole-home surge protective device	1	ea	$285.00	$285.00
Panel replacement labor Remove old panel, mount new, transfer and label all circuits, torque all terminations	1	job	$2,400.00	$2,400.00
AFCI/GFCI breakers where the inspector requires them Unit price; final count confirmed at inspection	8	ea	$58.00	$464.00
Permit and inspection (estimated, at cost)	1	ea	$185.00	$185.00
Utility disconnect and reconnect coordination Included	1	ea	$0.00	$0.00

Subtotal	$5,094.00
Sales tax (example rate 7%)	$151.83
Estimate total	**$5,245.83**
Deposit to schedule and order equipment (30%)	**$1,573.75**

OPTIONAL — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Generator inlet and interlock kit	1	ea	$690.00	$690.00
Dedicated 240 V circuit for a future EV charger	1	ea	$780.00	$780.00
Drywall patch and paint around the new panel	1	ea	$220.00	$220.00

NOTES AND TERMS

- Price assumes the panel stays where it is. Relocating the panel or service is a different scope.
- Power will be off for most of one day; we schedule around you and the utility.
- If existing branch circuits turn out damaged or unsafe during the transfer, we'll show you and price repairs before continuing.
- Payment schedule: 30% deposit; balance when the final inspection passes.

How to pay: Deposit by card or bank transfer (ACH) through the pay link on your deposit invoice.

Customer signature — I accept this estimate and its terms

Date