Wattleby Electric LLC

Licensed electrical contractor · Lic. #EC-00000

48 Commerce Loop
Oak Haven, GA 30500
(706) 555-0128 · office@wattleby.example

INVOICE

No. **INV-1508**

Date November 11, 2026

Terms Due on receipt

BILL TO

Kevin Osei
1205 Birchwood Dr
Oak Haven, GA 30500
(706) 555-0176 · k.osei@example.com

Permit: E-26-03118

Inspection: Passed Nov 11, 2026

Level 2 EV charger circuit and kitchen GFCI replacements

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
60 A two-pole breaker	1	ea	$78.00	$78.00
6 AWG copper conductors in EMT conduit Panel to garage wall, surface-mounted	46	lin ft	$9.50	$437.00
EV circuit labor Load calculation; run circuit; mount and terminate the customer-supplied charger; test	1	job	$520.00	$520.00
GFCI receptacle replacement, kitchen countertop Device included	3	ea	$95.00	$285.00
Panel directory updated and circuits labeled Included	1	ea	$0.00	$0.00
Electrical permit and inspection (passed through at cost)	1	ea	$110.00	$110.00

Subtotal	$1,430.00
Sales tax (example rate 7%)	$36.05
Total	**$1,466.05**
Balance due	**$1,466.05**

TEST RESULTS

Test	Result
Voltage at charger terminals	241 V
Charger current limit set to	48 A (continuous load on a 60 A circuit)
Kitchen GFCIs (3)	Trip and reset correctly

NOTES AND TERMS

- Load calculation done before install: the existing 200 A service has capacity for the new circuit.
- Workmanship warranty: 1 year on our wiring and terminations. The charger's warranty is with its manufacturer (customer-supplied).
- Payment due on receipt.

How to pay: Card or bank transfer (ACH) through the pay link.

Customer signature — work completed

Date

Sample invoice — every name, address and price on it is fictional, and the tax is an example: which lines are taxable depends on your state.