Thermal Line Insulation

Attics · Walls · Crawlspaces · Air sealing

604 Furnace St
Kingsfield, KY 40300
(859) 555-0166 · office@thermalline.example

ESTIMATE

No. **EST-0412**
Date November 4, 2026
Valid until December 4, 2026

PREPARED FOR

Nolan and Ruth Whitaker
33 Sassafras Hill
Kingsfield, KY 40300
(859) 555-0153 · whitaker.home@example.com

Attic top-up (R-49 added) and crawlspace floor insulation

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Attic air sealing Top plates, penetrations, chases, light boxes	1	job	$650.00	$650.00
Blown cellulose, R-49 added over the existing layer	1,400	sq ft	$1.70	$2,380.00
Rafter baffles at the eaves	30	ea	$6.50	$195.00
Insulate and weatherstrip attic hatch	1	ea	$125.00	$125.00
Crawlspace: R-19 batts between floor joists, supported	1,400	sq ft	$1.45	$2,030.00

Subtotal	$5,380.00
Estimate total	**$5,380.00**
Deposit to schedule (25%)	**$1,345.00**

OPTIONAL — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Remove and dispose of rodent-contaminated insulation About 300 sq ft near the eaves; billed by the area actually removed	300	sq ft	$1.25	$375.00
Extend bath fan ducts to the exterior	2	ea	$165.00	$330.00

NOTES AND TERMS

- Before quoting, we checked the attic for vermiculite insulation and knob-and-tube wiring and found neither. If either turns up during the work, we stop until the right specialist has dealt with it.
- Target levels follow ENERGY STAR's recommendations for climate zone 4A: add R-49 over the existing 3–4 inches in the attic, and R-19 under the floor. Final thickness, settled thickness and bag counts go on your installation record.
- Existing recessed lights not rated for insulation contact get covers or a clearance dam.

How to pay: Deposit by card or bank transfer (ACH) through the pay link on your deposit invoice.

Customer signature — I accept this estimate and its terms

Date