Thermal Line Insulation

Attics · Walls · Crawlspaces · Air sealing

604 Furnace St
Kingsfield, KY 40300
(859) 555-0166 · office@thermalline.example

INVOICE

No. **INV-0397**
Date November 11, 2026
Terms Due on completion

BILL TO

Rosalind Meyer
1504 Buckeye Ln
Kingsfield, KY 40300
(859) 555-0124 · r.meyer@example.com

Attic air sealing and blown-in insulation — R-49 added

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Attic air sealing Top plates, plumbing and wiring penetrations, chase openings, light boxes	1	job	$650.00	$650.00
Rafter baffles at the eaves	26	ea	$6.50	$169.00
Blown fiberglass insulation, R-49 added Over the existing layer (about R-11), for about R-60 in total	1,250	sq ft	$1.55	$1,937.50
Attic hatch: insulated cover, dam and weatherstrip	1	ea	$125.00	$125.00

Subtotal	$2,881.50
Total	**$2,881.50**
Balance due	**$2,881.50**

INSTALLATION RECORD (FTC R-VALUE RULE, 16 CFR 460.17)

Item	Value
Coverage area	1,250 sq ft
Insulation type	Loose-fill fiberglass
Initial installed thickness	17.5 in. (from the product's bag chart)
Minimum settled thickness	17 in. (from the product's bag chart)
R-value	R-49
Number of bags used	41

NOTES AND TERMS

- Installation record dated and signed by the installer below; a matching attic card is stapled near the hatch.
- No sales tax line: many states treat a contractor who installs materials as their consumer, taxed when the materials are bought — check your state's rules.
- Workmanship warranty: 1 year.

How to pay: Card or bank transfer (ACH) through the pay link, or check.

Installer signature — installation record above

Date

Customer signature — work completed

Date