Ridgeback Plumbing & Drain

Licensed & insured · Lic. #P-00000

2210 Foundry St, Suite B
Wenzel Falls, WI 53500
(608) 555-0142 · billing@ridgeback.example

ESTIMATE

No. **EST-1186**
Date November 10, 2026
Valid until December 10, 2026

PREPARED FOR

Ethan and Priya Marsh
77 Quarry Rd
Wenzel Falls, WI 53500
(608) 555-0129 · marsh.home@example.com

Whole-house repipe — PEX-A, single-story home with crawlspace

Replace the home's galvanized supply piping with PEX-A on a home-run manifold, from the main shut-off to every fixture. Work is done from the crawlspace with small access openings in walls where needed. Water will be off for part of two days.

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
PEX-A pipe, fittings and hangers 1-inch main to the manifold; 1/2-inch home runs	1	lot	$1,480.00	$1,480.00
Home-run manifold, 14 ports, with isolation valves	1	ea	$395.00	$395.00
Repipe labor — 14 home runs plus the main Home runs to the kitchen sink, 2 bath sinks, 2 tub/showers and the washer (hot and cold each) and 2 toilets; water heater and hose bibs fed from the main; pressure test; old lines capped and abandoned in place	1	job	$3,600.00	$3,600.00
New 1-inch main shut-off ball valve	1	ea	$145.00	$145.00
Wall access openings, cut clean and rough-patched Up to 8 openings; finish patch and paint not included	8	ea	$45.00	$360.00
Permit and inspection (estimated, passed through at cost)	1	ea	$150.00	$150.00

Subtotal	$6,130.00
Sales tax (example rate 5.5%)	$111.10
Estimate total	**$6,241.10**
Deposit to schedule and buy materials (30%)	**$1,872.33**

OPTIONAL — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Pressure-reducing valve Recommended: the static pressure test during the walk-through read 92 psi	1	ea	$385.00	$385.00
Replace hose bibs with frost-free sillcocks	2	ea	$135.00	$270.00
Finish patch, texture and paint at each access opening	8	ea	$95.00	$760.00

NOTES AND TERMS

- Price assumes clear crawlspace access. If we find conditions nobody could see — rotted joists, buried lines, earlier unpermitted work — we stop, show you, and price the change in writing before going on.
- Unit prices if needed: openings beyond the 8 included, $45 each (unused openings credited); an added fixture connection, $150 each.
- Not included: drywall finishing and paint (see optional lines), fixture replacement, water heater replacement, flooring or landscape repair.
- Payment schedule: 30% deposit to schedule; balance due when the final inspection passes.
- Pipe prices move with the market, so this estimate is good until the date above.

How to pay: Deposit by card or bank transfer (ACH) through the pay link on your deposit invoice.

Customer signature — I accept this estimate and its terms

Date